

AD-A034 244

MCDERMOTT (J RAY) CO INC NEW ORLEANS LA
ENGINEERING DESIGN CALCULATIONS MONO-MOORING SYSTEM. VOLUME 3. --ETC(U)
1966


F/6 13/10

DA-44-009-AMC-841(T)

NL

UNCLASSIFIED

1 OF 2
AD 34244



ENGINEERING
DESIGN CALCULATIONS
MONO-MOORING SYSTEM

VOLUME 3

APPENDIX A
to
FINAL REPORT

Contract No. DA-44-009-AMC-841(T)
U. S. ARMY MATERIEL COMMAND
ENGINEER RESEARCH AND DEVELOPMENT LABORATORIES
FORT BELVOIR, VIRGINIA

J. RAY McDERMOTT & CO., INC.
Saratoga Building
New Orleans, Louisiana

1966

SECTION I

SWIVEL DESIGN


PROJECT 2971

12-10-64

W.P.

MONO MOORING SYSTEM

PROPOSAL # 1
SWIVEL DESIGN




PROJECT 2971

12-11-64
WAP

MONO MOORING SYSTEM

PROPOSAL #2
SWIVEL DESIGN




PROJECT 2971
LAB ORDER 56017

12-14-61
W.F.P.

MONO MOORING SYSTEM

PROPOSAL #3
SWIVEL DESIGN



PROJECT 2971


1-11-65

WJ

MONO MOORING SYSTEM

PROPOSAL # 4

SWIVEL DESIGN



MESSINGER BRG CO

MR BOB CRAIG

PHIL. PA.

GA-6-7515

COMPUTATION SHEET
ENGINEERING DEPARTMENT

J. RAY MCDERMOTT & Co., INC.

MCD 5011

COMPANY

U.S. ARMY - ERDL

FIELD

SHEET NO.

24

WELL NO.

DATE

4/29/65


DRAWING NO.

10.56017

COMPUTER

WAF

SCHEMATIC DIAGRAM



COMPUTATION SHEET
ENGINEERING DEPARTMENT

MCD 5011

J. RAY McDERMOTT & Co., INC.

COMPANY

U.S. ARMY - ERDL

FIELD

SHEET NO.

1 of

PROJECT

MONO MOORING SYSTEM - DECK PLANS

WELL NO.

DATE


4/22/65

DRAWING NO.

OFFSET DIAGRAM

COMPUTER

WAF



COMPUTATION SHEET
ENGINEERING DEPARTMENT

MCD 5011
COMPANY

J. RAY McDERMOTT & Co., INC.

SUBJECT

DRAWING NO.



FIELD

SHEET NO.

WELL NO.

DATE

COMPUTER



ENGINEERING DEPARTMENT
COMPUTATION SHEET

MCD 5036


J. RAY McDERMOTT & CO., INC.

COMPANY	U.S. Army - ERDL			SHEET NO.	1 of 1
SUBJECT	MONO MOORING SYSTEM - OVERBOARD HOSE CONNECTION				
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE		
J.O. 56017	WAF		8/11/65		

HOSE LAY 7


15°
2.3

SECTION



JOB NO. 56017

SKETCH NO.



STRESS
RELIEVED

TEST
PRESSURE

No. REQ'D

MARK NO. *FPS-1R*

ISO. REF.

REV.

CHKD.

DWG. REF. *USA 2971-547-870*

REV.

DRWN.

DATE: 6-9-65

[illegible]

MATERIAL CHECK:

[illegible]


MATERIAL CHECK:

[illegible]

[illegible]

MATERIAL CHECK:

CUSTOMER <i>U.S. ARMY - ERDL</i>	CUSTOMER JOB NO.	JOB NO. <i>56017</i>
ADDRESS	CUSTOMER ORDER NO.	SKETCH NO.



		STRESS RELIEVED		TEST PRESSURE
No. REQ'D	MARK NO.	ISO. REF.	REV.	CHKD.
2	FSP - 3	DWG. REF. USA 2971-541 870	REV.	DRWN.
				DATE. 8/10/65

[illegible]


CUSTOMER *U.S. Army - E.R.D.L*

ADDRESS

CUSTOMER JOB NO.
CUSTOMER ORDER NO.

JOB No. **56017**

SKETCH NO.



NOTE: - BOLT HOLES
STRADDLE &
ALL FEES

**STRESS
RELIEVED**

TEST PRESSURE

No. REQ'D

MARK NO.

150. REF.

REV.

CHKD.

2

MARK NO. *FSP-4*

DWG. REF. *USA 2971 SM7 870*

REV.

DRWN.


DATE. 8/10/65

FIT-UP:

[illegible]

JOB NO.

SKETCH NO.



CHECKED:

**STRESS
RELIEVED**

TEST.
PRESSURE

No. REQ'D

MARK NO. FSP-5

ISO. REF.

REV.

CHKD.

DWG. REF. *USA 297-517 870*

REV.

DRWN.

DATE. 8-11-65

FIT-UP:

[illegible]

COMPUTATION SHEET
ENGINEERING DEPARTMENT

MCD 5011

J. RAY McDERMOTT & CO., INC.

COMPANY

U.S. ARMY - ERDL

FIELD

SHEET NO.

ECT

MONO MOORING SYSTEM - CARGO PIPING

WELL NO.

DATE

8/11/65

DRAWING NO.

J.O. 56017 OVERBOARD SPOOL PE LGT.

COMPUTER

WAP

LOCATION WATER
DEPTH

BUOY HULL
FEEL BOARD

SPOOL # SPOOL PE LGT.

50'

5.8'

FSP-5

1.22' (1'-2 $\frac{5}{8}$ "

60'

5.5'

FSP-5

.92' (0'-11 $\frac{1}{16}$ "

70'

5.2'

FSP-5

.62' (0'-7 $\frac{7}{16}$ "

80'

4.7'

NONR

.12' (0'-1 $\frac{7}{16}$ "

90'

4.5'

NONR

-.07' (-0'- $\frac{13}{16}$ "

100'

5.8'

FSP-5

1.22' (1'-2 $\frac{5}{8}$ "

110'

5.4'

FSP-5

.82' (0'-9 $\frac{13}{16}$ "

120'

5.0'

FSP-5

.42' (0'-5 $\frac{1}{16}$ "

130'

4.7'

NONR

.12' (0'-1 $\frac{7}{16}$ "

140'

4.2'

NONR

-.38' (-0'-4 $\frac{9}{16}$ "

150'

3.9'

NONR

-.68' (-0'-8 $\frac{3}{16}$ "

NOTE: -

SPOOL PE LGT BASED ON HOSE CONNECTING POINT

2'-3" ABOVE WATER LINE.

COMPUTATION SHEET
ENGINEERING DEPARTMENT

J. RAY McDERMOTT & Co., INC.

MCD 5011
COMPANY

U.S. Army - ERDL

FIELD

SHEET NO.

PROJECT

Mono Mocking System - Flaring

WELL NO.

DATE

DRAWING NO.

10.5417

Pipe & Conch Cap. Reinf.

COMPUTER

WAF etrie

PIPE WALL:-

200 psi

125°F

$$\text{Thickness} = t_m = \frac{PD}{25 + 24P} + C$$

$$t_m = \frac{200 \times 30}{(2 \times 25,500) + (2 \times 4 \times 200)} + .06 = \frac{6000}{51,000 + 160} + .06 = .178$$

INTERSECTION REINFORCEMENT:-

$$\text{REINF. AREA REQD} = (A_R = t_h d_1)(2 - \sin \beta)$$

$$A_R = (.178 \times 17)(2 - \sin 32^\circ 50') = 4.459$$

REINFORCEMENT

$$A_1 = (T_h - t_h)(d) = (.500 - .178)17 = 5.57$$

$$A_2 = 2(L_4)(T_b - t_b) = 2(1.25)(.500 - .178) = .66$$

$A_1 + A_2 = 5.57 + .66 = 6.23$ WHICH
IS GREATER THAN A_R THEREFORE
NO REINFORCEMENT REQUIRED

COMPUTATION SHEET
ENGINEERING DEPARTMENT

MCD 5011

J. RAY McDERMOTT & CO., INC.

COMPANY

U.S. ARMY ERDL

FIELD

SHEET NO.

SUBJECT

MONO MOUNTING SYSTEM - PIPING -

WELL NO.

DATE

DRAWING NO.

10.56017

BRANCH COLL. REINFORCEMENT

COMPUTER

WAP

REINFORCEMENT AREA REQUIRED

$$A_R = (t_h d_1)(2 - \sin \beta)$$

$$A_R = (.375 \times 17)(2 - \sin 32^\circ 50') = 6.37(1.45) = \underline{9.25 \text{ sq. in.}}$$

REINFORCEMENT

$$\text{IN HEADER} = A_1 = T_h - t_h (d) = (.500 - .375)(17) = 2.1 \text{ sq. in.}$$

$$\text{IN BRANCH} = A_2 = T_b - t_b (2)(L_4) = (.500 - .375)(2)(1.25) = .31 \text{ sq. in.}$$

$$\text{IN REINF. COLLAR} = A_3 = 2(t_c)(W) = 2(.500)(6.5) = 6.5 \text{ sq. in.}$$

$$A_1 + A_2 + A_3 = 2.1 + .31 + 6.5 = \underline{8.91 \text{ sq. in.} + WELDING} \\ = \underline{9.25"}$$

REINFORCEMENT COLLAR =

$$6.5" \text{ WIDE} = W$$

$$.500" \text{ THICK} = t_c$$

J. RAY McDERMOTT & Co., Inc.

SHEET NO

U. S. ARMY - ERDL

104



MONO MOORING SYSTEM - SINGLE, DESIGN #3


DATE _____

✓ O. 56017

WAP

4-21-65





OFFSET
DIMENSIONS


ENGINEERING DEPARTMENT
COMPUTATION SHEET

MCD 14003


J. RAY McDERMOTT & CO., INC.

COMPANY	U.S. ARMY - ERDL		SHEET NO	2 of
SUBJECT	MONO MOORING SYSTEM - DECK PILING ALBERT DESIGN			
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE	
JO. 56017	WAP		4-22-65	

PLAN



ALBERT DESIGN #3



J. RAY. McDERMOTT & Co., Inc.

COMPANY

SHEET NO.


SUBJECT

DRAWING ~~NUMBER~~


COMPUTER

CHECKED BY

DATE _____



PERGT. DESIGN #3




ENGINEERING DEPARTMENT
COMPUTATION SHEET
MCD 14003

J. RAY McDERMOTT & CO., INC.


COMPANY	U.S. ARMY - ERDL			SHEET NO	2 of
SUBJECT	MONO MOORING SYSTEM - FLOW SWIVEL PIPING				
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE		
10. 56017	WAP		3-29-65		

PLAN



PIPE DESIGN #1

65



COMPANY

U.S. ARMY - ERDL

SHEET NO.

1 of 1

SUB-LET

MONO PROCKING SYSTEM

Final Design #1

NUMBER

COMPUTER

CHECKED BY

DATE

NO 56014


W.P.

3-29-65

NOTE

FOR PLAN VIEW
SEE SHEET 2
OF SAME DATE

ELEVATION



ENGINEERING DEPARTMENT
COMPUTATION SHEET
MCD 14003


J. RAY MCDERMOTT & CO., INC.

COMPANY U.S. ARMY - ERDL	SHEET NO 1 of 1
SUBJECT MONO MOUNTING SYSTEM - SWIVEL DESIGN #2	
DRAWING NUMBER JC 56017	DATE 4-21-65
COMPUTER WAP	CHECKED BY

NOTE



FOR PLAN VIEW
SEE SHEET 2
OF SAME DATE

ELEVATION



SIGN 2

SWITCH 5000
S&B 21ST STANT
DATE 3-8-65
150 ME1




DEFSER
DIMENSIONS

TO SUB.
HOSE


2

COMPANY	U.S. ARMY - ERDL		SHEET NO	301
SUBJECT	MONO MOORING SYSTEM - FLOW SWIVEL PILING D			
DRAWING	10.56017	COMPUTER	WAP	CHECKED BY
			DATE	4/20/65

ELEVATION



PIPING DESIGN #2



COMPANY	U.S. ARMY - ERDL		SHEET NO	21
SUBJECT	MONO MOORING SYSTEM - FLOW SWIVEL PIPING DESIGN			
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE	
J.O. 56017	WAP		4-20-65	

PLAN

(N.T.S.)

16" TRIPLE RICH EARS
REINFORCED RUBBER
FOR 2000 PSI SERVICE

30' DIA
BODY HULL

16" STD 90° EL-L.R.

PIPE SUPPORT

16" STD PIPE

16"-150" ASA
W.N. FIG

PIPE SUPPORT

16" BUTTERFLY V
(BETWEEN FLS TYPE)

7'-9½"

KLINGBE
FL 120

16'-8"

SPRING DESIGN #2

TRIPLE ARCH EARTH.
REINFORCED RUBBER
FOR ZONE SERVICE

16" STD 45° ELL

18"x16" STD
90° Red Ell - L.R.

SUPPORT

16" 150# ASA
W.N. FEG

TRIM

16" STD 45° ELL
LONG TAN. BOTH ENDS
(ONE END TRIMMED)

37"

29 1/2"

14"

KISTINE
14" 120

36 3/16"

57"

57"

2

COMPANY

U.S. ARMY - ERDL

SHEET NO

SUBJECT

MONO MOORING SYSTEM - SWIVEL DESIGN for 150

DRAWING NUMBER

J.O. 56017


COMPUTER

WAP

CHECKED BY

DATE

3-25-65



NOTE: -

1. ALL SURFACES WHICH O RINGS FORM DYNAMIC SEAL TO BE 16 RMS
2. STATIC O RING SEAL TO BE 32 RMS
3. TIR TO 30.000" max


SWIVEL ASSM

AD CREVIS

RADIAL ROLLER B.R.G.

Having

X. FIRE BELLER SAC



TYPICAL SEAL ASSAY.

ENGINEERING DEPARTMENT
COMPUTATION SHEET

J. RAY MCDERMOTT & CO., INC.

COMPANY

U.S. ARMY - E.R.D.L.

SHEET NO

1 of 1

PROJECT

MONO MOORING SYSTEM - SWIVEL DESIGN

NUMBER

10 56017


COMPUTER

WJP

CHECKED BY

DATE

2-25-65



SWIVEL ASSY

55

50* 25110 W.N. Fig

Cap Brews


LUBRICATING FITTING
(DOWN BUT DO PHASE FOR CLARITY)

MISSINGER X BENDING

SWING HOUSING

WASE SEAL
(RING)

ASME - IN FIG



TYPICAL SEAL ASSM.

2

U.S. Army E.R.D.L.

4 of 4

MONO MOORING SYSTEM PRELIMINARY SKETCH

DRAWING NUMBER

COMPUTER

CHECKED BY

DATE

WJP

1-13-65

16 SID AIR FIXED (SHOUL ROTATES WITH THIS LINE)

O RING SEAL

41,000 PSI OUTER PASSAGE
61,000 PSI INNER PASSAGE

18,600 PSI
EITHER DIRECTION

18 X 16 L.R.
RED. EEL

30 X 16 SR
RED. EEL

O RING SEAL (TWO)

MESSINGER X
(TYP. TABLE)

UNION & SERVICE AIRWAYS

INNER PASSAGE 125 PSI

OUTER PASSAGE 125 PSI

12" E

OPERATING CONDITIONS

for 100 PSI SERVICE

1. FLOW IN OUTER PASSAGE ONLY

VERTICAL THRUST = 41,000^{lb}
 OVERHUNG LOAD = 18,600^{lb} @ 40"

2. FLOW IN BOTH PASSAGES

VERTICAL THRUST = 61,000^{lb}
 OVERHUNG LOAD = 22,000^{lb} @ 40"


3. FLOW IN INNER PASSAGE

LOADS EQUAL OR LESS THAN
 CONDITION 1.

NOTE - ROTATION TO BE

ALMOST STATIC CONDITION

COMPANY	U.S. ARMY E.R.D.L.	SHEET NO	5 of
SUBJECT	MONO MOORING SYSTEM PRELIMINARY SKETCH		
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE
			2-22-65



Vertical Thrust for 150 PSI

Vertical Thrust

39,770 #
Inner Direction

SEAL (110)

INNER X ROLLER B.L.G.
(Type 7-10-1)

OPERATING CONDITIONS

for 150 PSI SERVICE

1. FLOW IN OUTER PASSAGE ONLY

VERTICAL THRUST = 61,225 #
OVERHUNG LOAD = 39,770 # @ 40" ±

2. FLOW IN BOTH PASSAGES

VERTICAL THRUST = 95,995 #
OVERHUNG LOAD = 58,850 # @ 40" ±

3. FLOW IN INNER PASSAGE

LOADS EQUAL OR LESS THAN
CONDITION 1.

NOTE: - ROTATION TO BE
ALMOST STATIC CONDITION

ENGINEERING DEPARTMENT
COMPUTATION SHEET

J. RAY McDERMOTT & Co., INC.

COMPANY

U.S. Army - ERDL

SHEET NO

1 of

SUBJECT

MONO MOORING SYSTEM - DYNAMIC Flow Loads on


DRAWING NUMBER

COMPUTER

CHECKED BY

DATE

1-4-65



NOTES: —

1. FLOW THRU INNER & OUTER PASSAGES TO BE 10,500 GPM EACH. TOTAL FLOW 21,000 GPM (39,000 BPH)
2. FLOW THRU EITHER PASSAGE OR BOTH DURING OPERATING PERIODS

loads on Swivel

REVISED for 150 PSI

SEE SHEET DATED 2/19 & 2/22

FORMULAS:

"BERNOULLI THEOREM"



$$P_x = -\rho Q (V_2 \cos \theta - V_1) + P_1 A_1 - P_2 A_2 \cos \theta$$

$$P_y = \rho Q V_2 \sin \theta + P_2 A_2 \sin \theta$$

Q = Flow cfs

ρ = DENSITY IN SLUGS PER CUBIC FT = Use 6.935 for WATER

A1 = AREA SQ FT

A2 = AREA SQ FT


V1 = VELOCITY FPS

V2 = VELOCITY FPS

P1 = PRESSURE LBS/SQ FT (100 PSI)

P2 = PRESSURE LBS/SQ FT

(I)



(Cont'd)

2

ENGINEERING DEPARTMENT
COMPUTATION SHEET
MCD 14003

J. RAY McDERMOTT & CO., INC.

COMPANY U.S. Army - E.R.D.L.		SHEET NO 2 of	
SUBJECT MORO MOORING SYSTEM - DYNAMIC FLOW LOAD ON			
DRAWING NUMBER	COMPUTER WAF	CHECKED BY	DATE 1-4-65

①


$$P_H = -1.935 \times 23.4 (8.3 \cos 90^\circ - 19.1) + 14,400 \times 1.23 - 14,400 \times 2.8 \cos 90^\circ$$

$$P_H = 865 + 17,700 - 0 = \underline{18,565 \text{ LBS}}$$

$$P_V = 1.935 \times 23.4 \times 8.3 \sin 90^\circ + 14,400 \times 2.82 \sin 90^\circ$$

$$P_V = 395 + 40,550 = \underline{40,925 \text{ LBS}}$$

②



$$P_H = 1.935 \times 23.4 (17.5 \cos 90^\circ - 19.1) + 14,400 \times 1.23 - 14,400 \times 1.3 \cos 90^\circ$$

$$P_H = 865 + 17,700 - 0 = \underline{18,565 \text{ LBS}}$$

$$P_V = 1.935 \times 23.4 \times 17.5 \sin 90^\circ + 14,400 \times 1.33 \sin 90^\circ$$

$$P_V = 770 + 19,150 = \underline{19,920 \text{ LBS}}$$

V.O. 56017

LEADS ON SURVIVAL

REVISOR

SEE NEW STRINGS

$$14,400 \times 2.8 \cos 90^\circ$$

$$2 \sin 90^\circ$$

$$4000 \times 1.3 \cos 90^\circ$$


$$3 \sin 90^\circ$$

1

2

COMPANY U.S. ARMY ERDL	SHEET NO 3 of
SUBJECT MONO MOORING SYSTEM - DYNAMIC FORCE FACTOR ON	
DRAWING NUMBER	COMPUTER WAP
CHECKED BY	DATE 1-4-65

III




$$P_x = -1.935 \times 23.4 (19.1 \sin 90^\circ - 19.1) + 14,400 \times 1.23 - 14,400 \times 1.23 \cos 90^\circ$$

$$P_x = 865 + 17,700 - 0 = \underline{18,565 \text{ LBS}}$$

$$P_y = 1.935 \times 23.4 \times 19.1 \sin 90^\circ + 14,400 \times 1.23 \sin 90^\circ$$

$$P_y = 865 + 17,700 = \underline{18,565 \text{ LBS}}$$

IV



$$P_x = -1.935 \times 23.4 (19.1 \cos 45^\circ - 19.1) + 14,400 \times 1.23 - 14,400 \times 1.23 \cos 45^\circ$$

$$P_x = 281 + 17,700 - 12,500 = \underline{2,481 \text{ LBS}}$$

10. 56017

FRAGILE ON SWIVEL

REVISION


See New Sketch

-14,400 x 113 cos 90°

LESS

3 sin 90°

5



100 x 113 x 45°

2

ENGINEERING DEPARTMENT
COMPUTATION SHEET
MCD 14003

J. RAY McDERMOTT & CO., INC.

COMPANY

U.S. Army E.R.D.L.

SHEET NO

9 of

SUBJECT

MONO MOORING SYSTEM - DYNAMIC FLOW FORCES ON SAVIN

DRAWING NUMBER

COMPUTER

009

CHECKED BY

DATE

1-5-65

(IV) cont'd

$$P_y = 1.935 \times 23.4 \times 19.1 \sin 45^\circ + 14,400 \times 1.23 \cos 45^\circ$$

$$P_y = 612 + 12,500 = \underline{13,112 \text{ LBS}}$$

V.O 56017

is in David

Received
Six Nov 1915

450

ENGINEERING DEPARTMENT
COMPUTATION SHEET
MCD 5015

J. RAY MCDERMOTT & CO., INC.

COMPANY		SHEET NO.	
SUBJECT <i>BERNOULLI THEOREM</i>			
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE

Formulas: -

$$P_x = -\rho Q (V_2 \cos \theta - V_1) + P_1 A_1 - P_2 A_2 \cos \theta$$

$$P_y = \rho Q V_2 \sin \theta + P_2 A_2 \sin \theta$$

ENGINEERING DEPARTMENT
COMPUTATION SHEET
MCD 5015

J. RAY McDERMOTT & CO., INC.

COMPANY		SHEET NO	
SUBJECT			
DRAWING NUMBER		COMPUTER	CHECKED BY
			DATE

30 x 16 Ell 90° flow 30 to 16

$$P_x = -\rho Q (V_2 \cos \theta - V_1) + P_1 A_1 - P_2 A_2 \cos \theta$$

$$= -1.935 \times 23.4 (19.1 \cos 90^\circ - 8.3) + 14,400 \times 2.8 - 14,112 \times$$

$$1.2 \cos 90^\circ$$

$$375 + 40,400 = 40,775 \text{ LBS}$$

$$P_y = \rho Q V_2 \sin \theta + P_2 A_2 \sin \theta$$

$$= 1.935 \times 23.4 \times 19.1 \times 1 + 14,112 \times 1.2 \times 1$$

$$= 856 + 16,900 = 17,756 \text{ LBS}$$

ENGINEERING DEPARTMENT
COMPUTATION SHEET
MCD 5015

J. RAY McDERMOTT & CO., INC.

COMPANY		SHEET NO	
SUBJECT <i>30 x 16 89° flow 30 to 16</i>			
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE

$$P_H = P Q (V_2 \cos \theta - V_1) + P_1 A_1 - P_2 A_2 \cos \theta$$

$$= 1.935 \times 23.4 (9.1 \cos 89^\circ - 8.3) + 14,400 \times 2.8 - 14,112 \times$$

$$1.2 \cos 89^\circ$$

$$390 + 40,400 - 282 = 40,508 \text{ LBS}$$

ENGINEERING DEPARTMENT
COMPUTATION SHEET

J. RAY McDERMOTT & CO., INC.

COMPANY		SHEET NO	
SUBJECT <i>30 x 16 Ell 90° flow 16 to 30</i>			
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE

$$R_x = -\rho Q (V_2 \cos 90^\circ - V_1) + P_1 A_1 - P_2 A_2 \cos \theta$$

$$= -1.935 \times 23.4 (8.3 \cos 90^\circ - 19.1) + 14,400 \times 1.2 - 100 \times 2.8 \cos 90^\circ$$

$$856 + 17,600 = 18,456$$



COMPUTATION SHEET
ENGINEERING DEPARTMENT

MCD 5011

J. RAY McDERMOTT & CO., INC.

COMPANY

U.S. ARMY ERDL

FIELD

SHEET NO.

1 of 1

TCT

MONO MOORING SYSTEM

WELL NO.

DATE

11/12/65

DRAWING NO.


105607 GUT LINE ARRGT.

COMPUTER

WAFETRIC

SECTION SHOWING PAGA REQUIRED
FOR HYDRAULIC & ELECTRICAL
SERVICE RUNS BETWEEN BUOY MACH'Y
COMPARTMENT AND CONTROL CONSOLE

CROSS SECTION



4 1/2" I.D.
GUT LINE
THRU UPPER
SWIRL UNIT

SECTION II

BUOY EQUIPMENT
AND SYSTEMS

COMPUTATION SHEET
ENGINEERING DEPARTMENT

4CD 5011

J. RAY MCDERMOTT & CO., INC.

COMPANY

FIELD

SHEET NO.

SUBJECT

WELL NO.

DATE

ING NO.

COMPUTER

CHAIN STOPPER DESIGN

PITCH DIA .852 D

WIRE DIA .148" = d , $d^3 = .0032$, $d^4 = .00048$

INITIAL TENSION = 10# = P_i

NO COILS = 64 = N

COIL LENGTH = 9.47"

LENGTH INSIDE HOOKS 12"

OUTSIDE DIA = 1"

$$\text{INITIAL TENSIONING STRESS} = S_i = \frac{2.55 PD}{d^3}$$

$$S_i = \frac{2.55 \times 10 \times .852}{.0032}$$

$$S_i = 6800 \text{ psi}$$

$$\text{SPRING RATE} = P = \frac{G d^4}{8 D^3 N}$$

$$P = \frac{9.5 \times 10^6 \times .00048}{8 \times .615 \times 64}$$

$$\frac{4500}{315}$$

$$P = 1415 \text{ \#/"} \text{ DEFLECTION}$$

$$\text{TORSIONAL STRESS} = S_t = (\text{USE } 75,000 \text{ MAX})$$

$$P_{\text{MAX}} = \frac{S_t \pi d^3}{16 R \frac{\pi}{4}}$$

$$P_{\text{MAX}} = \frac{75000 \times 3.14 \times .0032}{16 \times .426 \times .615}$$

$$\frac{755}{785}$$

$$P_{\text{MAX}} = 96.2 \text{ \# (MAX ALLOWABLE SPRING LOAD)}$$

$$\text{BENDING STRESS} = S_b = \frac{32 PR}{\pi d^3}$$

$$S_b = \frac{32 \times 96.2 \times .426}{3.14 \times .0032}$$

$$S_b = 139,000 \text{ psi}$$

$$\text{DEFLECTION} = F = \frac{P_{\text{MAX}} - P_i}{P}$$

$$F = \frac{96.2 - 10}{1415} = .06"$$

2/12/65
wsp

PITCH DIA .838 = D

Wire Dia .162 = d, $d^3 = .0042$; $d^4 = .0007$

INITIAL TENSION = 10 # = P

No COILS = 79 = N

Coil LENGTH 12.96"

LENGTH INSIDE HOOKS $15\frac{1}{4}"$ OVER LIMITS FOR STRECH

OUTSIDE DIA 1"

$$\text{INITIAL TENSIONING STRESS} = S = \frac{2.55 PD}{d^3}$$

$$S = \frac{2.55 \times 10 \times .838}{.0042}$$

$$S = 5100 \text{ psi}$$

$$\text{SPRING RATE} = P = \frac{G d^4}{8 D^3 N}$$

$$P = \frac{9.5 \times 10^6 \times .0007}{8 \times .59 \times 79}$$

$$P = 17.9 \text{ #/" DEFLECTION}$$

$$\text{TORSIONAL STRESS} = S_T \text{ (USE 75,000 MAX)}$$

$$P_{MAX} = \frac{S_T \pi d^3}{16 \times R \times \frac{1}{2}}$$

$$P_{MAX} = \frac{75000 \times 3.14 \times .0042}{16 \times .419 \times 1.15}$$

$$\frac{995}{2.7}$$

$$P_{MAX} = 128 \text{ # (MAX ALLOWABLE SAFE LOAD)}$$

96.5

$$\text{BENDING STRESS} = S_B = \frac{32 PR}{\pi d^3}$$

$$\text{INITIAL TENSIONING STRESS} = S = \frac{2.55 PD}{d^3}$$

$$S = \frac{2.55 \times 10 \times .838}{.0042}$$

$$S = 5100 \text{ psi}$$

$$\text{SPRING RATE} = P = \frac{G d^4}{8 D^3 N}$$

$$P = \frac{9.5 \times 10^6 \times .0007}{8 \times .59 \times 79}$$

$$P = 17.9 \# / \text{" DEFLECTION}$$

$$\text{TORSIONAL STRESS} = S_T \quad (\text{USE } 75,000 \text{ MAX})$$

$$P_{\text{MAX}} = \frac{S_T \pi d^3}{16 \times R \times \frac{1}{2}}$$

$$P_{\text{MAX}} = \frac{75000 \times 3.14 \times .0042}{16 \times .419 \times 1.15}$$

$$\frac{998}{27}$$

$$P_{\text{MAX}} = 128 \# \quad (\text{MAX ALLOWABLE SAFE LOAD})$$

75.5

$$\text{BENDING STRESS} = S_B = \frac{32 PR}{\pi d^3}$$

$$S_B = \frac{32 \times 128 \times .419}{3.14 \times .0042}$$

$$S_B = 130,000 \text{ psi}$$

$$\text{DEFLECTION} = F = \frac{P_{\text{MAX}} - P_i}{P}$$

$$F = \frac{128 - 10}{17.9} = 6.6 \text{"}$$

$$\frac{118 - 10}{17.9}$$

COMPUTATION SHEET
ENGINEERING DEPARTMENT


J. RAY McDERMOTT & Co., INC.

COMPANY U.S. Army - ERDL	FIELD	SHEET NO. 1 of 1
PROJECT Munic Mocking System - Chain Strapper	WELL NO.	DATE 2/12/65
DRAWING NO. J.O 56017	COMPUTER VMP	

MATERIAL:- SAE 30316 STAINLESS OR A3140 TITANEL

WORKING SPECIFICATIONS:-

OUTSIDE DIA	1"
PITCH DIA	.852"
WIRE DIA	.148"
INITIAL TENSION	10 LBS
NO COILS	64
COIL LENGTH	9.47"
LENGTH INSIDE HOOKS	12"
APPROX SPRING RATE	14.5 LBS/" DEFLECTION
TOTAL DEFLECTION	6" MAX




NOTE: TOTAL LOAD @ 6" DEFLECTION 95# ± 5%


ENGINEERING DEPARTMENT
COMPUTATION SHEET
MCD 14003

J. RAY MCDERMOTT & CO., INC.

COMPANY	U. S. ARMY - ERDL			SHEET NO
SUBJECT	MONO MOORING SYSTEM - ANCHOR CHAIN			
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE	
	WOF			

3" DIA STUD LINK CHAIN.
(BOLT OR EQUAL)






1

2

ENGINEERING DEPARTMENT
COMPUTATION SHEET
MCD 14003

J. RAY McDERMOTT & CO., INC.

COMPANY U.S. ARMY - ERDL	SHEET NO. 1
SUBJECT MONO MOORING SYSTEM - BUOY DRAFT	
DRAWING NUMBER V.O. 56017	COMPUTER WAP
CHECKED BY	DATE 4-23-65



LOCATION WATER DEPTH	BUOY DRAFT (PRE LOAD)	PRE LOAD
60'	6.7'	
100'		
150'	11.5'	

NOTE: MOORED LOAD INCREASES TOTAL
DRAFT OF BUOY.

5

2

COMPUTATION SHEET
ENGINEERING DEPARTMENT

MCD 5011

J. RAY McDERMOTT & CO., INC.

COMPANY

FIELD

SHEET NO.

SUBJECT

WELL NO.

DATE

DRAWING NO.

COMPUTER

BOGIE WHEEL DESIGN

ENGINEERING DEPARTMENT
COMPUTATION SHEET

MCD 14003

J. RAY McDERMOTT & CO., INC.

COMPANY

U.S. ARMY ERD.L

SHEET NO

1 of

SUBJECT

MONO TRACKING SYSTEM - Bogie Wheel Loads

DRAWING NUMBER

COMPUTER



W.R.D.

CHECKED BY

DATE

1-14-65

INNER RACE FOR HORIZONTAL LOAD



PRELIMINARYPRESSURES & AREAS OF CONTACT / BOGIELOAD

$$\text{TOTAL LOAD} = 300,000 \#$$

$$\text{ACTIVE WHEELS} = 6$$

$$\text{LOAD/WHEEL} = \frac{300,000}{6} = 50,000 \#$$

formula: -

LOAD CAPACITY PER LIN. INCH OF WHEEL
(AISC) H 5-19

$$F_p = \left(\frac{F_y - 13,000}{20,000} \right) 66,000$$

AREAS OF CONTACT AND PRESSURES
(KENT 8-36)

$$S = .591 \sqrt{F_p E \left(\frac{d_1 + d_2}{d_1 \times d_2} \right)}$$

$$b = 2.15 \sqrt{\frac{F_p}{E} \left(\frac{d_1 \times d_2}{d_1 + d_2} \right)}$$

$$\delta = \frac{2(1-\nu^2)}{E} \frac{F_p}{\pi} \left(\frac{2}{3} + \log_e \frac{2d_1}{b} + \log_e \frac{2d_2}{b} \right)$$

F_y = YIELD STRENGTH OF STEEL = 46,000

F_p = WHEEL LOAD CAPACITY PER LIN. IN.


S = MAX PRESSURE AT & CONTACT (WHEEL)

E = MODULUS OF ELASTICITY = 30,000,000

δ = COMBINED DEFORMATION OF BOTH
WHEEL & RAIL

ALL FIGURES IN INCHES & POUNDS

COMPANY	U.S. ARMY - ERDL			SHEET NO	2 of 7
SUBJECT	MONO MOORING SYSTEM - BOGIE WHEEL LOADS				
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE		
	WJD		1-15-65		



TOTAL DEFORMATION OF BOTH BODIES

$$y = \frac{2(1-.3^2)}{E} \frac{F_D}{\pi} \left(\frac{2}{3} + \log_e \frac{2d_1}{b} + \frac{2d_2}{b} \right)$$

$$y = \frac{2(1-.3^2)}{30 \times 10^6} \times \frac{11,100}{3.14} \left(\frac{2}{3} + \log_e \frac{2 \times 12}{.063} + \frac{2 \times 108}{.063} \right)$$

$$y = .003''$$

LOADS

PRELIMINARYALLOWABLE LOAD PER INCH OF FACE WIDTH OF WHEEL

$$F_p = \left(\frac{K_t - 13,000}{20,000} \right) 660 d_1$$

$$F_p = \left(\frac{42,000 - 13,000}{20,000} \right) 660 \times 12 = 11,500 \#$$

FACE WIDTH OF WHEEL

$$W = \frac{\text{LOAD}}{F_p}$$

$$W = \frac{50,000}{11,500} = 4.35" \text{ USE } \underline{\underline{4 \frac{1}{2}"}}$$

$$\text{ACTUAL } F_p = \frac{\text{LOAD}}{W}$$

$$\frac{50,000}{4.5} = 11,100 \#$$

MAX. UNIT STRESS @ CONTACT POINT

$$S_c = .591 \sqrt{F_p \times E \left(\frac{d_1 + d_2}{d_1 \times d_2} \right)}$$

$$S_c = .591 \sqrt{11,100 \times 30 \times 10^6 \left(\frac{12 + 108}{12 \times 108} \right)}$$

$$S_c = 103,000 \text{ PSI}$$

CONTACT WIDTH

$$b = 2.15 \sqrt{\frac{F_p}{E} \left(\frac{d_1 \times d_2}{d_1 + d_2} \right)}$$

$$b = 2.15 \sqrt{\frac{11,100}{30 \times 10^6} \left(\frac{12 \times 108}{12 + 108} \right)}$$

$$b = .063"$$

ENGINEERING DEPARTMENT
COMPUTATION SHEET

MCB 14003

J. RAY McDERMOTT & CO., INC.

COMPANY

U.S. ARMY - ERDL

SHEET NO

3 of

SUBJECT

MONO MOORING SYSTEM - BOGIE WHEEL LOAD

DRAWING NUMBER

COMPUTER

WJP

CHECKED BY

DATE

1-18-65

OUTER RACE FOR VERTICAL LOAD



MAX. UNIT STRESS @ CONTACT POINT

$$S_c = .591 \sqrt{\frac{F E}{d}} = .591 \sqrt{\frac{7200 \times 30 \times 10^6}{12}}$$

$$S_c = 79,000 \text{ PSI}$$

CONTACT WIDTH

$$b = 2.15 \sqrt{\frac{F d}{E}} = 2.15 \sqrt{\frac{7200 \times 12}{30 \times 10^6}}$$

$$b = .115$$

LOAD

PRELIMINARYLOAD

TOTAL VERTICAL LOAD = 195,000 #

USE SAME DIA & WIDTH WHEEL
AS FOR HORIZONTAL LOAD
12" DIA X 4" WIDE

 $F_p = 11,500 \text{ #/lin in. from Sheet 2}$ ALLOWABLE LOAD PER WHEEL

$$F = 11,500 \times 4 = 46,000 \text{ #}$$

NO WHEELS REQD.

$$N = \frac{195,000}{F} = \frac{195,000}{46,000} = 4.24$$

USE MIN 5 WHEELS
DESIGN IN PAIRS, USE 6 WHEELS

LOAD PER WHEEL

$$\text{LOAD} = \frac{195,000}{6} = 32,500 \text{ #}$$


ACTUAL F_p =

$$\frac{\text{LOAD}}{N} = \frac{32,500}{4.5} = 7,200 \text{ #/in}$$


ENGINEERING DEPARTMENT
COMPUTATION SHEET
MCD 14003

J. RAY MCDERMOTT & CO., INC.

COMPANY	U.S. ARMY - ERDL		SHEET NO	4 of
SUBJECT	MONO-MOORING SYSTEM - BOGIE DESIGN			
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE	
	WAF		1-21-65	




PLAN

PRELIMINARYPLANELEVATION

P


COMPANY	U.S. ARMY - ERDL		SHEET NO	5 of
SUBJECT	MONO MOORING SYSTEM - BOGIE DESIGN			
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE	
	WAP		1-21-65	



SECTION A-A

56017

PRELIMINARY




SECTION B-B

2

COMPANY U.S. ARMY - ERDL SHEET NO 6 of 6
SUBJECT MONO MOORING SYSTEM - BOGIE DESIGN
DRAWING NUMBER _____ COMPUTER _____ CHECKED BY _____ DATE _____

NOTE

SHAFT CONT'D TO
BACK SUPPORT
PER STRUCTURAL
DESIGN



OUTER RACE BOGIE WHEEL

for VERTICAL FORCES

56017

PRELIMINARY

STAINLESS SHAF

ATING DECK STRUCTURE

$\frac{5}{16}$ " CAP SCREW

$\frac{1}{2}$ " CAP SCREW

GARLOCK SEAL
53X7559R2

AMERICAN ROLLER BAG
ACS-271

$\frac{1}{2}$ " CAP SCREW

STAINING RING

CEL

ENGINEERING DEPARTMENT
COMPUTATION SHEET

J. RAY McDERMOTT & CO. INC.

COMPANY

SUBJECT

USA ERDL

9

MOND-MOONING SYSTEM


JOB 56017

6. LINE 15



7/21/65

PRELIMINARY DESIGN OF SUPPORT FOR OUTER-
FACE ROSSIE WHEELS

CONSIDER



16.5



THICKNESS OF BASE AS



$$A = 32.5(2) = 65 \text{ } \checkmark$$

$$S = 12 \text{ } \checkmark \text{ for } 70,000 \text{ tensile}$$

$$B = 16.3 + 32.5 = 48.8 \text{ } \checkmark$$

TRY 3/4" PIN

$$d = \sqrt[3]{\frac{17}{.098 \times 5}}$$

$$M = 32.5(5) = 162.5 \text{ } \checkmark \text{ } < 101.1 \text{ } \text{O.K.}$$

$$d = \sqrt[3]{\frac{162.5}{.098 \times 12}}$$

THICKNESS OF BASE AS

$$d = 4.3 \text{ } \checkmark \text{ pin}$$

$$t = \frac{48.8}{104} = .469 \text{ } \checkmark \text{ } \text{use } 5/8 \text{ } \checkmark \text{ } \text{thick}$$

$$t = \frac{13}{5 \times 4} = \frac{48.8}{12 \times 4.3} = .945 \text{ } \checkmark$$

CONSIDER BENDING IN THE GIRDER

65k

$$\text{MAX } M = 3(65)(6.5) = 1270 \text{ "k}$$

DETERMINE MOMENT OF INERTIA

$$I = \frac{7(23)^3}{12} = 7097$$

$$\frac{55(21.5)^3}{12} = 4555$$

$$I = 2,542 \text{ in}^4$$

$$f = \frac{Mc}{I} = \frac{1,270(11.5)}{2,542} = 575 \text{ ksi}$$

$$I = \frac{7(23)^3}{12} = 7097$$

$$= \frac{575(22)^3}{12} = 5102$$

$$I = 1,995 \text{ in}^4$$

$$f = \frac{Mc}{I} = \frac{1,270(11.5)}{1,995} = 281 \text{ ksi } 2.1\%$$

NOTE: PUT STIFFENERS NEAR PIN LOCATION TO DISTRIBUTE SHEAR

COMPUTATION SHEET
ENGINEERING DEPARTMENT

CD 5011

J. RAY MCDERMOTT & CO., INC.

COMPANY

FIELD

SHEET NO.

SUBJECT

WELL NO.

DATE

ENGINEERING NO.

COMPUTER

BUOY SYSTEMS

COMPANY **U.S. ARMY - ERDL** SHEET NO.
PROJECT **Mobile Manpower System - Derrick Hoist & Arch**
NUMBER **J.O. 56017** COMPUTER **WJP** CHECKED BY **WJP** DATE **5-4-65**

AIR IS HYDRAULIC

AIR

IR. #K6U

SPACE REQUIREMENT (Prime Mover & Pulley Unit)
(HOIST)

46 1/2" L. x 31 1/2" W. x 86" H.

WEIGHT

(Prime Mover & Pulley Unit) DRY
(HOIST)
(HYDRAULIC FLUID)

5000 #
1315 #
NONE

HOIST CAPACITY (LINE PULL)

(DRUM CAP.) 1/4 CHAIN
(LINE SPEED 1/2 MIN)

10,700 # 1/2" CHAIN
200 FT for Rating 410' H.
65' / MIN.

(PRESSURE & GPM)
(H.P. REQ'D)

125 PSI & 30 cfm

BRAKE CAPACITY

CONTROLS

MANUAL VALVE - IN GEAR

FLOW LINES

(SUPPLY)
(RETURN)

1 1/2" IPS
NONE

CLEANLINESS REQUIREMENTS

FILTER ON COMP. INTAKE

SYSTEM COMPLEXITY

SINGLE LINE SYSTEM
HIGH FLOW LUBRICATOR

FLEXIBILITY & RELIABILITY

IMMEDIATE RESPONSE
EXT. GRADE SUCCEED TO C

& MACHINERY

HYDRAULIC SYSTEM

HYDRAULIC

K6U

MARCO #W0960

GEAROMATIC #22S

31 1/2" L. x 36" H.

36" L. x 33" W. x 28 3/4" H.

31 1/2" L. x 23 1/2" W. x 21 1/4" H.

000 #

3600 #

15 #

1000 #

NE

130 GAL @ 2.5 % = 475 #

825 #

200 GAL @ 4.5 % = 1500 #

0 # 1/100 GPM
for RATING (4.0' FEET)
P.A.N.

(1500 PSI MAX)
14,800 # BACK DRAIN
10,000 # FILL DRAIN

(1500 PSI)
10,500 #
9,100 #

(1900 PSI MAX)
22,000 # BACK DRAIN
12,700 # FILL DRAIN

PSI & 30 CFM

88 GPM 200 FT 46 GPM
50 / MIN 67 / MIN BACK D.
70 / MIN 123 / MIN FILL D.
1500 PSI & 46 GPM
54 HP

46 GPM 212 FT 65 GPM
40 / MIN 60 / MIN BACK D.
72 / MIN 104 / MIN FILL D.
1500 PSI & 46 GPM
54 HP 59 HP

LINE INTEGRAL

15,000 # LINE FILL
MEAN DRAIN CAP.
MANUAL 4 WAY - 3 POSITION
PRESSURE REGULATING CONTROLS

MANUAL 4 WAY - 3 POSITION
PRESSURE REGULATING CONTROLS

IPS

1 1/2" IPS
1 1/4" IPS

1 1/2" IPS
1 1/4" IPS

COMP. FILL

25 MICRON FILTER

25 MICRON FILTER

LINE SYSTEM
LUBRICATOR

SUPPLY & RETURN LINES
PRESSURE CONTROLS

SUPPLY & RETURN LINES
PRESSURE CONTROLS

RESPONSE
SUCCESSION TO COMMAND

IMMEDIATE RESPONSE
DESIGNED FOR MARINE
SERVICE

IMMEDIATE RESPONSE
USED FOR CRUISE OR INDUSTRIAL

ENGINEERING DEPARTMENT
COMPUTATION SHEET

J. RAY McDERMOTT & CO., INC.

COMPANY

U.S. ARMY - ERDL

SHEET NO

SUBJECT

MOORING SYSTEM - DERRICK HOIST & MACHINE

NUMBER

I.O. 56017

COMPUTER

WAP

CHECKED BY

DATE

5-4-65

AIR VS HYDRAULIC

AIR

IR #K6U

HOIST FINISH

DERRICK HOIST SPEC. CHART

OTHER UNITS TO POWER

NONE

COST - (PRIME MOVER & POWER UNIT)
(HOIST)
(HYDRAULIC FLUID)

} 18,791.00
NONE

Check and
Pay

MACHINERY

HYDRAULIC SYSTEM (Contd)

HYDRAULIC

60

5.5. CATER

VE

MARCO #W0960

GALV. W/ 5.5. FASTNERS

POSSIBLE AIR COMPRESSOR

GEARMATIC 225

DETENT COAT SPEC ORDER

POSSIBLE AIR COMPRESSOR

CONTROL CAB
1.7.790

9,354⁰⁰ LOSS CONTROL
COSTANT

6454⁰⁰ 1st. ONIO
2900⁰⁰ 1st. SEATTLE
75⁰⁰ / 100 GAL

{ 14,791⁰⁰ INC CONTROL
CHAINA
75⁰⁰ / 100 GAL

2

COMPUTATION SHEET
ENGINEERING DEPARTMENT

MCD 5011

J. RAY MCDERMOTT & Co., INC.

COMPANY

U.S. ARMY ERDL

FIELD

SHEET NO.

SUBJECT

MONO MOORING SYSTEM -

WELL NO.

DATE

DRAWING NO.

10.56017 - ENG. LOAD ON BOLTS @ LAUNCHING

COMPUTER

WAP

CONDITIONS: ENGINE G.M. TYPE 371 HE Ceclad
DRY WT APPROX 1800#
G.G. ABOVE MOUNTS APPROX 19"
DISTANCE BTWN. MOUNTS 24" center
TOTAL BOLTING 6 - $\frac{1}{2}$ " ϕ
LAUNCH IMPACT ASSUME 5g

$$1800 \times 5 = 9000 \# \text{ LOAD @ LAUNCH ON BOLTS}$$

$$\text{SHEAR/BOLT} = \frac{9000}{6} = 1500 \#$$

$$\text{MOMENT} = 9000 \times 19 = 171,000 \text{ " \#}$$

$$\text{TENSION IN BOLTING} = \frac{171,000}{24} = 7120 \#$$

$$\text{LOAD/TENSION/BOLT} = \frac{7120}{3} = 2370 \#$$

$$\frac{1}{2} \text{ " BOLT IN SHEAR ALLOWABLE } 2.6 \text{ K}$$

$$\frac{1}{2} \text{ " BOLT IN TENSION ALLOWABLE } 4 \text{ K}$$

NOTE:

WHILE BOLTING IS ADEQUATE TO HOLD ENGINE ON FOUNDATION DURING BOY LAUNCHING THE ENGINE MFG. ADVISES THAT MOUNTS & FRAME ARE OF CAST IRON AND ADVISE THAT LATERAL BRACING FROM ENGINE LIFTING BOLTS TO BOY OVERHEAD SHOULD BE INSTALLED TO RELIEVE LOAD FROM CAST FRAME WORK. A FRACTURE IN THE FRAME WOULD REQUIRE REBUILDING THE ENGINE INSIDE THE BOY WHICH COULD BE DIFFICULT.

ENGINEERING DEPARTMENT
COMPUTATION SHEET

MCD 8036

J. RAY MCDERMOTT & CO., INC.

COMPANY

U.S. Army - ERDL

SHEET NO.

1 of 1

SUBJECT

MONO MOORING SYSTEM - HYDRAULIC PUMPING UNIT

NUMBER

J.O. 56017


COMPUTER

WJP

CHECKED BY

DATE


6-2-65



ENG. MOUNT.

E

ENG UNIT



ELEVATION

N.T.S.

ENGINEERING DEPARTMENT
COMPUTATION SHEET

J. RAY McDERMOTT & CO., INC.

COMPANY

U.S. ARMY - ERDL.

SHEET NO.

2 of

SUBJECT

MONO MOORING SYSTEM - HYDRAULIC PUMPING UNIT

DRAWING NUMBER

J.O. 56017


COMPUTER

NAP

CHECKED BY

DATE


6-3-65



PLA

N.T.S.

Unit
5



PLAN

N.T.S.


ENGINEERING DEPARTMENT
COMPUTATION SHEET

MCD 5036

J. RAY MCDERMOTT & CO., INC.

COMPANY <i>U.S. ARMY - E.R.D.L.</i>	SHEET NO. <i>1 of</i>
SUBJECT <i>MONO. MOORING SYSTEM - PIPING SYSTEMS - COOLING WATER</i>	
DRAWING NUMBER <i>JO. 56017</i>	COMPUTER <i>WAP</i>
CHECKED BY	DATE <i>7-20-65</i>

HEAT EXCHANGER RAN



AD-A034 244

MCDERMOTT (J RAY) CO INC NEW ORLEANS LA
ENGINEERING DESIGN CALCULATIONS MONO-MOORING SYSTEM. VOLUME 3. --ETC(U)
1966


DA-44-009-AMC-841(T)

F/G 13/10

NL

UNCLASSIFIED

2 OF 2
AD
A034244




END

DATE
FILMED
2-77

COOLING WATER

RAW WATER SCHEMATIC



COMPANY

U.S. ARMY - ERDL

SHEET NO.

2 of

SUBJECT

MONO MOORING SYSTEM - PIPING SYSTEMS - FUEL OIL

DRAWING NUMBER

JO. 56017

COMPUTER


WAP

CHECKED BY

DATE


7-20-65

FUEL OIL SCHE



S - FUEL OIL

SCHEMATIC



COMPANY

U.S. Army - ERDL

SHEET NO

3 of 1

SUBJECT

MONO MOORING SYSTEM PIPING SYSTEMS - BILGE

DRAWING NUMBER

NO. 56017

COMPUTER


WAF

CHECKED BY

DATE


7-21-65

BILGE PIPING SC.



BILGE

ING SCHEMATIC





NOTE: -

FITTINGS USED TO
PIPE THIS SYSTEM
SHOULD BE KEPT TO
A MINIMUM FOR
PRESSURE DROP
REASONS.

COMPANY	U.S. Army - ERDL			SHEET NO	4 of 4
SUBJECT	MONO MOORING SYSTEM - PIPING SYSTEMS - ENG. EXHAUST				
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE		
JO. 56017	WAP		7-21-65		


EXHAUST PIPING



EXHAUST

PIPING SCHEMATIC

PER
MMU-6



COMPUTATION SHEET
ENGINEERING DEPARTMENT

MCD 5011

J. RAY McDERMOTT & CO., INC.

COMPANY

U.S. ARMY ERDL

FIELD

SHEET NO.

141

SUBJECT

DIESEL ENGINE EXHAUST LOCATION

WELL NO.

DATE

11/30/65

DRAWING NO.

COMPUTER

WJP

$$O-X = 5-6\frac{3}{8}"$$

$$O-Y = 9'-4\frac{15}{16}"$$

$$O \text{ to } a = 180" - .09" = 179.91"$$

$$a \text{ to } c = 49.66"$$

$$c \text{ to } e = 5.87"$$

$$\angle = 27^{\circ}-52'-30"$$



$$d \text{ to } c = 5.87 \times \tan \angle = 5.10$$

$$d \text{ to } e = 5.87 \div \cos \angle = 6.64"$$

$$O \text{ to } Y = 127.75 \times \cos \angle = 112.93"$$

$$Y \text{ to } d = 127.75 \times \sin \angle = 59.72"$$

$$Y \text{ to } e = 59.72 + 6.64 = 66.36"$$



REFERENCE

BODY HULL

PLAN

$$2-S = 5.87"$$

$$RAD = 180"$$

COMPANY	U.S. ARMY - ERDL			SHEET NO	4
SUBJECT	MONO MOORING SYSTEM - HYDRAULIC				
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE		

PUMP CALCULATIONS :-

REQD - 38 GPM
1500 PSI @ WINCH

$$\text{HYD. H.P.} = \frac{\text{GPM (HP)}}{1714} = \frac{38 \times 1500}{1714} = 33.3 \text{ HP}$$

$$\text{BRAKE H.P.} = \frac{\text{GPM (HP)}}{1714 \times E} = \frac{38 \times 1500}{1714 \times .80} = 41.5 \text{ HP}$$

DRIVE ENGINE CALCULATIONS :-

371 GPM @ 1800 RPM

RATED H.P. = 97
CONT'S H.P. = 75

471 GPM @ 1800 RPM

RATED HP = 133
CONT'S H.P. = 101

FUEL CONSUMPTION

371 GPM @ 1800 = .46 LBS/BHP/HR

$$.46 \times 41.5 = 19.1 \text{ LBS/HR} = \frac{19.1}{7} = 2.73 \text{ GPM}$$

471 G.M. @ 1800 = .447 LBS/BHP/HR

$$.447 \times 41.5 = 18.6 \text{ LBS/HR} = \frac{18.6}{7} = 2.66 \text{ GPM}$$

BHP OF ENG 14% LOWER ON "CITE" FUEL

COMBUSTION AIR REQUIREMENTS

371 G/M @ 1800 RPM 319 SCFM

471 G/M @ 1800 RPM 425 SCFM

2

COMPUTATION SHEET
ENGINEERING DEPARTMENT

CD 5011
COMPANY

J. RAY McDERMOTT & CO., INC.

FIELD

SHEET NO.

SUBJECT

WELL NO.

DATE

ING NO.

COMPUTER

MACHINERY AND POWER

ENGINEERING DEPARTMENT
COMPUTATION SHEET

J. RAY McDERMOTT & CO., INC.

NOB 14003

COMPANY	U.S. ARMY - ERDL			SHEET NO
SUBJECT	MONO MOORING SYSTEM - MACHINERY			
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE	
	WAP		1-26-65	

MACHINERY:

NAVIGATIONAL AIDS

LIGHTS	10 WATTS
HORN	320 WATTS
BEACON	

(BLOW OFF)

ILLUMINATION FOR WORKING 2000 WATTS

BILGE PUMP (100 GPM) $1\frac{1}{2}$ HP

DECK ROTATING MACHINERY (HYDRAULIC) (2 HP)

HYDRAULIC PUMPING SET 22 HP

DERRICK WINDLASS (HYDRAULIC) (20 HP)

MAX ELECTRICAL LOAD: (WATTS)

NAVIGATIONAL AIDS	330
ILLUMINATION FOR WORKING	2000
BILGE PUMP	1119
HYDRAULIC PUMPING SET	16512

19,961

19,961
1,000

19.9 KW

(RADAR BEACON NOT INCL.)

56017

TTTS
TTTS

(BLDN 2500
OFF 18 SEC)

WATTS

HP

HP)

HP

HP)

2

ENGINEERING DEPARTMENT
COMPUTATION SHEET

J. RAY McDERMOTT & CO., INC.

MCD 14003

COMPANY	U.S. ARMY - ERDL			SHEET NO
SUBJECT	MONO MOORING SYSTEM - MACHINERY			
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE	
	WAP		1-26-65	

NAVIGATIONAL AIDS: - (ALL TO U.S. COAST GUARD)

LIGHTS: - 200 mm BODY & STRUCTURE LANTERN
MULTI-LAMP & CHANGER TYPE
WATERTIGHT, GASKETED CONSTRUCTION
360° VISIBILITY - CLEAR LENS
12 VOLT DC

HORN: - OMNI-DIRECTIONAL - 2 MILE RANGE
WATER TIGHT GASKETED CONSTRUCTION
BATTERY OPERATED
12 VOLT DC

BATTERIES: - DRI PRIMARY TYPE OR
LEAD ACID TYPE
N.CAD - CHARGING RATE TYPE (ALT)

MISC: - NECESSARY ACCESSORIES
TO MEET REQUIREMENTS FOR
AIDS AS SET FORTH IN SPEC

ILLUMINATION: -

LIGHTING IN MACHINERY COMPARTMENT
AND ON DECK OF BODY TO
TO BE DONE AT NIGHT FOR
A VESSEL & MAINTAINING 50
REQUIRED

COAST GUARD REQUIREMENTS)

RED LIGHTS (WALLACE & TIERMAN, TORLUND'S SPECIALTIES, ETC)
RED TYPE
CONSTRUCTION
CLEAR LENS

2 MILE RANGE (AUTOMATIC BEACON INC, TORLUND'S SPECIALTIES, ETC)
CONSTRUCTION

OR
THE TYPE (ACT) REQUIRE DEFINITE PROTECTION AGAINST EXPLOSION

FOR RED
LIGHTS FOR OPERATING
IN IN SPECS

VERY COMPARTMENTS
BODY TO ALLOW WORK
LIGHT FOR BOTH MOVING
STATION BODY AS MAY BE

ENGINEERING DEPARTMENT
COMPUTATION SHEET

MCD 14003

J. RAY McDERMOTT & CO., INC.

COMPANY	U.S. ARMY - E.R.D.L.		SHEET NO.	3 of
SUBJECT	Mooring System - MACHINERY			
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE	
	WAP		1-26-65	

BILGE PUMP : (TO U.S. Coast Guard Regu

CENTRIFUGAL TYPE WITH 3/4" IN
MIN 2" SUCTION
1 1/2 HP Elec. Motor Drive
MIN PUMPING CAP. 100 GPM

DECK ROTATING MACHINERY:-

HYDRAULIC MOTOR, DRIVE
REDUCTION.
WHEN NOT USED TO ROTATE
MUST BE DISENGAGED
FREE SWING OF DECK
BY SEA CONDITION.

HYDRAULIC PUMP SET:-

VARIABLE VOLUME, AXIAL
COMPACT WITH ELEC
REQUIREMENTS 18 G
@ 1500 PSI, ALLOWABLE
TO 2000 PSI
INTEGRAL 60 GPM
MOTOR CHARACTERISTIC 20
OIL COOLER NOT REQD

DERRICK WINDLASS:-

HYDRAULIC OPERATED
LINE PULL WITH HORN
LINE SPEED WITH HORN

GUNNO REQUIREMENTS)

WITH SELF PRIMING

MOTOR DRIVE

100 GPM @ 35' HEAD

MOTOR DRIVEN GEAR

TO ROTATE DECK

ENGAGED TO ALLOW

OF DECK AS REQUIRED

CONDITIONS

EQUIP, AXIAL PISTON TYPE (DENISON, VICKERS, RACINE SAE, ETC)

WITH ELECTRIC MOTOR & COUPLING

13 GPM DELIVERY

ALLOWABLE PRESSURE RANGE

60 GAL RESERVOIR

208 V, 3 ϕ 60 CYC A.C. (APPROX 20 HP REQUIRED)

NOT REQUIRED

OPERATED WITH AUTOMATIC BRAKING (GEORANTIC, MARCO ETC)

WITH MEAN DRUM CAP. 17,000 LBS (FURNISH)

WITH MEAN DRUM CAP. 23 fpm (FURNISH)

2

COMPANY

U.S. ARMY - ERDL

SHEET NO

4 of 4

SUBJECT

MOORING SYSTEM - BASIC MACHINERY PLAN

DRAWING NUMBER


COMPUTER

WAP


CHECKED BY

DATE

1-28-65



NAVIGATIONAL AIDS





BUOY MACHINE

Proposal #1

RADIO BEACON or
EDGE TRANSMITTER

OUTSIDE DECK ILLUMINATION

COMPARTMENT ILLUMINATION




HYDRAULIC PUMP UNIT

AIR COMPRESSOR
(REQUIREMENT NOT DETERMINE)


MACHINERY

2

COMPANY	U.S. ARMY - ERDL		SHEET NO	5 of
SUBJECT	MONO MOORING SYSTEM - BASIC MACHINERY POWER - P			
DRAWING NUMBER	COMPUTER	CHECKED BY	DATE	
	WAP		1-29-65	




NAVIGATIONAL AIDS



BUOY MACHINERY


PROPOSAL #2

WIRING




2

COMPANY U.S. Army - ERDL SHEET NO 6 of
SUBJECT MONO MOORING SYSTEM BASIC MACHINERY POWER
DRAWING NUMBER _____ COMPUTER WAF CHECKED BY _____ DATE 1-29-65



NAVIGATIONAL AIDS




ENGINE DRIVEN HYDRAULIC PUMP

BUOY MACHINERY

Power House #3

ON OR
SPINOR



DERRICK WINCH

DECK ROTATING MACHINERY

BILGE PUMP

AIR COMPRESSOR
(15 G.P.S.)

ENGINEERING DEPARTMENT
COMPUTATION SHEET

J. RAY McDERMOTT & CO., INC.

COMPANY

U.S. Army - ERDL

SHEET NO

7 of

SUBJECT

MONO MOORING SYSTEM - BASIC MACHINERY & Piping - 12

DRAWING NUMBER



COMPUTER

WAP

CHECKED BY

DATE

1-30-05



CON. 42
SPRING 44



COMPARTMENT ILLUMINATION



Air Commander
(if reqd)

2

ENGINEERING DEPARTMENT
COMPUTATION SHEET

J. RAY McDERMOTT & Co., INC.

MCD 14003

COMPANY

U.S. Army - ERDL

SHEET NO

804

SUBJECT

MONO MACHINERY SYSTEM - BASIC MACHINERY POWER - BUREAU

DRAWING NUMBER


COMPUTER

WAP


CHECKED BY

DATE

3-1-65



NAVIGATIONAL AIDS



ENGINE DRIVEN HYDRAULIC PUMP


BUOY MACHINERY

POWER - MACHINE #5

CON OR
SPINDER



TOPSIDE DECK ILLUMINATION



WIRES PASS THRU
FLOW SWIVEL HERE


ILLUMINATION



COMPARTMENT ILLUMINATION

DECK WINCH

DECK ROTATING WINCH




BILGE PUMPS


AIR COMPRESSOR
(IF REQD)

2

COMPANY *U.S. ARMY - ERDL* SHEET NO *9 of*
SUBJECT *MONO MARKING SYSTEM - BASIC MACHINERY & POWER*
DRAWING NUMBER COMPUTER *WAF* CHECKED BY DATE *3-24-65*



NAVIGATIONAL AIDS




BUOY MACHINERY

Power Proposal #6

DERRICK WINCH

BACK ROTATING WINCH



COMPARTMENT LIGHTING


AIR COMPRESSOR
(if Reqd)

AIR DEPOLARIZED
PRIMARY CELLS
BATTERY BANK




BILGE PUMPS

2



INSTALLATION EQUIPMENT

VICKERS NO



①	RESERVOIR 88 GAL NOM. CAP.	
②	PUMP-VANE TYPE-FIXED VOLUME	35V25A-1C10-132
③	STRAINER	50S-149-M-3-P4
④	RELIEF VALVE	CG-06-F-10
⑤	UNLOADING VALVE	RG-06-F4-10
⑥	CHECK	C2-825
⑦	CHECK	C2-830-S19
⑧	DIRECTIONAL VALVE	CM3N01-KBL-20
⑨	MOTOR-PISTON TYPE-FIXED VOLUME	MFA120-30
⑩	RELIEF VALVE	CG-06-F-10
⑪	DIRECTIONAL VALVE	CM2N02-KDL-20
⑫	DIRECTIONAL VALVE	DG17S4-012A-41
⑬	OIL COOLER	OCA-30-10
⑭	FILTER	OFM-202
⑮	NEEDLE VALVE	
⑯	AIR BLEED VALVE	ABT-02-19

2



SECTION III

RIGID ARM APPROACHES

ENGINEERING DEPARTMENT
COMPUTATION SHEET
MCD 14003

J. RAY McDERMOTT & CO., INC.

COMPANY	U.S. ARMY - ERDL	SHEET NO	1 of 1
SUBJECT	Mono Mooring System -		
U.O. 56017	COMPUTER	CHECKED BY	DATE
	WAF		3-4-65



TANKER

MOORING LINES TO KEEP
BUOY AT TANKER SIDE

MANIFOLD

BOOM TO HANDLE HOSE TO TANKER

HOSE CONNECT
TO MANIFOLD

BOUY

2

ENGINEERING DEPARTMENT
COMPUTATION SHEET

J. RAY McDERMOTT & CO., INC.

MCB 16003

COMPANY

U.S. Army - E.R.D.L.

SHEET NO.

1 of 1

PROJECT

MONO MOORING SYSTEM - RIGID ARM

APPRO

PROJECT NUMBER

J.O. 56017

COMPUTER

WAP

CHECKED BY

DATE

2/24/65

Buoy

MAIN MOORING LINES

AVOY

SWIVEL


STRUCTURAL MEMBERS
TO BE USED AS PING LINE
FROM TANKER TO BUOY

TANKER LIGHT


TANKER LOADS

PROBLEM AREA FOR
SHALLOW WATER INSTALLATION.
ANCHOR CHAIN INTERFERENCE


APPROACH #1-A




COMPANY	U.S. ARMY - ERDL.			SHEET NO	1 of 1
TITLE	Mound Mooring System - RIGID ARM				APP
DRAWING NUMBER	10 56017	COMPUTER	RAF	CHECKED BY	
				DATE	2/25/65



APPROACH # 1-B




ONE OF ARM USED AS
A LINE TO BOAT.





ENGINEERING DEPARTMENT
COMPUTATION SHEET
WD 14003

J. RAY McDERMOTT & CO., INC.

COMPANY U.S. ARMY - ERDL	SHEET NO 1 of 2
SUBJECT 170000 MOORING SYSTEM - RIGID ARM	
PROJECT NUMBER 10. 56017	COMPUTER WAP
	CHECKED BY WAP
	DATE 2-25-65



APPROACH #4-A



COMPANY U.S. ARMY - ERDL SHEET NO. 2012
PROJECT MARCO MOORING SYSTEM
DRAWING NUMBER V.O. 56017 COMPUTER WJF CHECKED BY WJF DATE 2-23-65

Beam SWIRL AREA - 500psi ALLOWABLE LOAD

$$\frac{300,000}{500} = 600 \text{ SQ IN. IN TENSION OR COMPRESSION}$$

$$DIA = \sqrt{\frac{600 \times 2}{\pi \times 1416}} = 19.5 \text{ MIN DIA + ALLOWANCE FOR}$$

BEAM - TENSION = 300K

$$AREA = \frac{300}{12} = 25 \text{ SQ IN}$$

Use 24" x 1.375 PIPE BRACE AS SHOWN FOR
24" API = 95#/FT

DECK PIN SHEAR = 300K

$$AREA = \frac{300}{10} = 30 \text{ SQ IN}$$

Use 4 1/2" PIN IN DOUBLE SHEAR

#4-R

CONDENSING

REWORK FOR SLOT

WORK FOR BENDING

2

ENGINEERING DEPARTMENT
COMPUTATION SHEET

Rev 5090

20' 15' 18'
J. RAY McDERMOTT & CO., INC.

COMPANY

U.S. ARMY ERDL

SHEET NO.

1

PROJECT

MANO-WARNING SYSTEM (RIGID ARM)

PROJECT NUMBER

COMPUTER


CHECKED BY

DATE


JOB 56012

ANDREWS

2/24/65



APPROACH #3-C



PROJECT U.S. Army - ERDL	SHEET NO 2012
TITLE Hand Hoisting System	
DESIGN NUMBER 1A. 56017	DATE 2-23-65
COMPUTER WJF	CHECKED BY

Base Level Area - 500mi Allowable Load

$$\frac{300,000}{500} = 600 \text{ kg in. in tension or compression}$$

$$D_{10} = \frac{1}{2} = \frac{600,000}{2,500,000} = 19.5 \text{ mm dia. + Allowance}$$

Beam - Tension = 300K

$$Area = \frac{300}{12} = 25 \text{ sq in.}$$

Use 24" x .375 Flange Brace as shown
24" dia. = 95,000 lb

Deck Pin Shear = 300K

$$Area = \frac{300}{10} = 30 \text{ sq in.}$$

Use 4 1/2" Pin in Double Shear

14-11

1
fano

2
e con...

3
e ...


4
... ..

0000

1. The first part of the document is a list of names and addresses.

2. The second part is a list of names and addresses.

3. The third part is a list of names and addresses.



$$I(\theta) = 64.5\%$$

$$2560,000(.1)$$

$$13326252)$$

